

# Crook County Road and Bridge Department

Morgan Ellsbury, Superintendent



PO Box 995 Sundance WY 82729 Phone: (307) 283-1441 Fax: (307) 283-2323

---

## **BID SPECIFICATIONS**

### **MOORCROFT FUEL STATION**

#### **BID DUE DATE:**

Bids must be received by the Road & Bridge Office no later than 5:00 PM on Wednesday September 19, 2012. Any bids received after that time will not be opened or considered. Wyoming Contractors will be awarded 5% preference.

#### **SCOPE OF WORK:**

Crook County is seeking bids for the construction of a fuel station at the Moorcroft County yard. The project will include the supply and installation of new products, no used items will be accepted. All components of the fuel station must be UL listed and meet or exceed the requirements of: Wyoming Department of Environmental Quality; Occupational Safety and Health Administration; and National Fire Protection Agency. Upon completion of the project an inspection will be performed. Payment will not be made until the inspector deems the system compliant with all applicable agencies.

The Fuel Station shall include the following components at minimum:

- A. (1) 2,000 gallon, cylindrical, double wall, horizontal tank with (2) 6-inch diameter emergency vents, lockable fill cap, inner wall leak detector gauge, tank painted white with proper combustible materials warnings and identification.
- B. (1) 30 gallon per minute 115/230V pump with gallon meter. (1) 1 inch diameter hose, 25 feet long and high flow automatic shut off nozzle with a fuel rated automatic retractable hose reel with swivel and breakaway fitting.
- C. (1) 30 micron high flow filtration system to be placed after the meter and before the hose reel.
- D. (1) 10 key operator with individual gallon meter for each key slot, or card reader with the same characteristics.
- E. (1) Visual tank level indicator with fractional markings (example  $\frac{1}{4}$ ,  $\frac{1}{2}$ ,  $\frac{3}{4}$ ) or gallon/inches markings to be seen from ground level on the front face of the tank.
- F. (1) twenty pound ABC fire extinguisher, to be mounted compliant with NFPA standards.
- G. (2.07) cubic yards of 4000 psi concrete formed, placed, and finished flat, 6'x14'x8" with 3/8" reinforcement bars tied on a 1 foot grid.
- H. The appropriate power source is provided at the site and all electrical work will be completed by Crook County's electrician, as well as the installation of an emergency shut-off switch.

**(Do not include electrical work in your bid price)**

# Crook County Road and Bridge Department

Morgan Ellsbury, Superintendent



PO Box 995 Sundance WY 82729

Phone: (307) 283-1441

Fax: (307) 283-2323

## BID FORM

Date \_\_\_\_/\_\_\_\_/\_\_\_\_

Company name\_\_\_\_\_

Company contact\_\_\_\_\_

Address\_\_\_\_\_

\_\_\_\_\_

Best Phone #\_\_\_\_\_

Business Fax\_\_\_\_\_

E-Mail\_\_\_\_\_

As the duly authorized representative of the above named firm, I submit these total bid prices and acknowledge that the project is scheduled to start approximately October 8, 2012.

|                        |    |
|------------------------|----|
| Moorcroft Fuel Station | \$ |
|                        |    |

Printed name\_\_\_\_\_

Authorized

signature\_\_\_\_\_Date\_\_\_\_\_

---

### OFFICE USE ONLY:

Bid Received Date:\_\_\_\_\_ All Required Documents Included:\_\_\_\_\_

Bid Award: YES / NO