

# SCOPE OF WORK

## OSHOTO FIRE HALL

### Project Location:

The Oshoto Fire Hall will be located in a rural part of Crook County about 2 miles west and 17 miles north of Moorcroft, Wyoming. This site is adjacent to County Highway #68, D Road.

### Project Description:

The Oshoto Fire Hall building will be forty-six feet (46') wide by eighty feet (80') long by sixteen feet (16') tall. The building structural system may be either a pre-engineered metal building (PEMB), or a Structural Insulated Panel (SIP) wood framed building. The siding, liner and roofing will be metal panels. The foundation will be a shallow system of cast-in-place concrete. The building floor and approach slabs will be reinforced cast-in-place concrete.

Building features will include five (5) sectional overhead doors, two (2) walk doors, four (4) windows, and a floor trench drain. The building will be heated and insulated.

There will be an administrative room and toilet in one corner of the building that will be finished by the volunteer fire-fighters.

The site work (except the approach slabs & sidewalks) will be performed by the volunteer fire-fighters.