

Moorcroft sidewalk and Parking lot scope of work

Removal and disposal of existing sidewalk, handrail and parking pads

Removal and disposal of tree stumps

Grade and prep base sloping away from the building and improve drainage on SW corner

4" concrete pad with #4 rebar on 2' center (34'x 60' 2040 ft²)

Install new sidewalk maintaining elevation at building

New 48' handrail (painted) built out of 1½" steel tubing and support post every 4'.
-Must be 34" from top of concrete to top of handrail

Proposals must break out the cost for:

Removal and disposal of old concrete, handrail and tree stumps

Grading and site prep

New finished concrete and labor

New handrail materials, labor and painting

Proposals can be emailed to Randy Gill at randyg@crookcounty.wy.gov , Mailed to PO Box 995 Sundance, WY 82729 or dropped off at the Road and Bridge office in the Courthouse in Sundance.

Bids are due Tuesday, May 3rd at Noon