

Moorcroft sidewalk and Parking lot scope of work

Removal and disposal of existing sidewalk, handrail and parking pads

Removal and disposal of tree stumps

Grade and prep base sloping away from the building and improve drainage on SW corner

4" concrete pad #4 rebar on 2' center (900 sq ft)

Install new sidewalk maintaining 2% grade for ADA and new handrail (painted).

Proposals must break out the cost for:

Removal and disposal of old concrete, handrail and tree stumps

Grading and site prep

New finished concrete and labor

New handrail materials, labor and painting

Proposals can be emailed to Randy Gill at randyg@crookcounty.wy.gov , Mailed to PO Box 995 Sundance, WY 82729 or dropped off at the Road and Bridge office in the Courthouse in Sundance.

PRE-BID MEETING to be held April 26, 2016 at 10:00 am at the Moorcroft Library jobsite to review the job and answer questions.

Bids are due May 3rd at Noon